

Complexe de la Romaine

ASPHALT CORE DAM Hydro-Québec Experience

by Jean-Pierre Tournier




Symposium du Comité Français des Barrages et Réservoirs

Marseille – 31 janvier 2019

- Hydro-Québec has built the first ACRD in North America, in 2008, on the Rupert diversion project in the James Bay area. The intention was to have a better understanding of that technology to apply it on the La Romaine Complex (north shore of the Saint-Lawrence River).
- The Nemiscau-1 dam has a height of 16,2 m with a length of 336 m at his crest. The maximum hydraulic head is 7,6 m due to a pond at his downstream toe. The construction started in June, 2008 and was completed by October, 2008.

Nemiscau 1 Dam – Typical cross section



For the asphalt core:

Thickness: 40 cm

Thickness of the layer after compaction: 22,5 cm

Maximum 3 layers per day

Nemiscau 1 Dam – Trial and test sections



- Good experience at Nemiscau dam; the contract allowed us to make trial tests and an in depth understanding of that technology.
- After that very good appropriation of the asphalt core technology, Hydro-Québec decided to go ahead with seven (7) asphalt core structures on La Romaine Complex.

Basin Area of La Romaine River

 Havre St-Pierre (HSP): 14 470 km²


• RO-1: 12 970 km²

• RO-2: 12 200 km²


• RO-3: 10180 km²

• RO-4: 8550 km²






Complexe de la Romaine Overview



Retaining structures of La Romaine 2 facility


Structure	Type	Height (m)	Crest lenght (m)	Asphaltic core volume (m³)	Fill volume (m³)
Dyke A 2	ACRD	31	144	1 040	88 300
Dyke B 2	ACRD	28	115	790	73 400
Dyke D 2	ACRD	48	728	6 330	666 000
Dyke E 2	ACRD	39	407	2 470	218 000
Dyke F 2	ACRD	84	423	10 700	1 947 000
Main Dam	ACRD	131	496	18 850	4 546 000
TOTAL				40 180	7 538 700




Typical ACRD cross section (Main Dam)


Romaine 2 – Main dam (July 2012)







Longitudinal section and concrete sill details (Main Dam)




Romaine 2 – Main dam (November 2014)




Romaine 2 – Dike F2 (May 2013)



Dike F2 - Longitudinal section and sill details





Romaine 2 - Dike F2 (November 2014)



Thickness of the asphalt core

- ➤ Main Dam: from 80 cm to 50 cm
- ➤ Dike F2: from 70 cm to 50 cm
- **➢ Dikes A2, B2, D2 and E2: 50 cm**

Layers of the asphalt core

- ➤ Thickness after compaction: 22,5 cm
- ➤ Maximum of 3 layers per day

Construction period for the asphalt core

▶11 months (2013 and 2014) with 2 general contractors and 4 core paving machines

- Impoundment started on May 10th, 2014 and the maximum level of the reservoir was reached November 7th, 2014.
- One year after impoundment (November 2015):
- The seepage through all the structures is very low and varies from 0 l/s to 2 l/s.
- For the dam the maximum settlement reached at the crest is 220 mm upstream and 40 mm downstream.


Seepage at RO-2 Dam

Reservoir water level (m)

Seepage flow measured at weir (L/sec)

Rainfall (mm)

DÉVERSOIR DE JAUGEAGE AU BARRAGE RO-2 DMB560_147




Displacements at RO-2 Dam Crest

Upstream/Downstream (mm)

Settlements (mm)


Longitudinal (mm)




Horizontal displacements during impoundment (topographic monuments at the crest of the dam)

Downstream (320 mm max) Upst


Upstream (250 mm max)



Settlements at RO-2 Dam Core Crest



Horizontal and vertical displacements at RO-2 Dam



Romaine 2 – Intake, Dikes D2, E2 and F2 (November 2014)




Survey monument (November 2015)

		Buried SM in core			
	ΔY max (mm) (Upstream/Downstream)		∆Z max (mm) Settlements		ΔZ max (mm) settlements
	Upstream side	Downstream side	Upstream side	Downstream side	
Dam	250	320	-220	-40	-90
Dyke A2	2	2	-1	-1	
Dyke B2	1	2	-0,5	-1	
Dyke D2	9	8	-1	-0,5	
Dyke E2	4	3	-2	-1	
Dyke F2	40	40	-36	-6	-13

Retaining ACRD structure of La Romaine 1 facility

Structure	Туре	Height (m)	Crest lenght (m)	Asphaltic core volume (m³)	Fill volume (m³)
Main Dam	ACRD	41	850	5 600	608 000

Typical cross section of the dam



Thickness of the asphalt core: 50 cm

Layers of the asphalt core

- ➤ Thickness after compaction: 22,5 cm
- ➤ Maximum of 3 layers per day

Construction period for the asphalt core

▶6 months (2014) with 1 general contractors and 2 core paving machines

Romaine 1 Dam (October and November 2014)










- Beginning of Reservoir Impoundment : September 22, 2015;
- Full Supply Level was reached on October 20, 2015;
- Reservoir First Filling Lasted 28 Days.
- Instrumentation data indicates very small displacements (maximum of 5 mm settlement) and negligible seepage flow during winter conditions.

Seepage at RO-1 Dam

Reservoir water level (m)

Seepage flow measured at weir (L/sec)

Rainfall (mm)



Displacements at RO-1 Dam

Upstream/Downstream (mm)

Settlements (mm)

Longitudinal (mm)

